



OCS 2019-001
ROAD REHABILITATION – VARIOUS LOCATIONS
Addendum No. 1

Issued: February 6, 2019

URGENT This Addendum shall be incorporated into the tender package and shall form a part of the contract documents. Please forward this document to whoever is in possession of the tender package

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Tender Package, and be governed accordingly.

1. Remove Document VI, page 8 and replace with REVISED Document VI, page 8 attached.
 - Item B.07 the unit should read m² and the quantity is 75 m²
 - Item B.08 the unit should read m² and the quantity is 75 m²

2. Remove Document VI, page 13 and replace with Document VI, REVISED page 13 attached.
 - Item F.08 unit should read ea.
 - Item F.09 unit should read l.m. and the quantity should be revised from 10 to 1,300

PART B

Line 9 North - Horseshoe Valley Road to Warminster Side Road

Item	Description	Unit	Estimated Quantity	Unit Rate	Total
B.01 SP 2.01	Pulverize existing asphalt 150mm	m2	23,310		
B.02 SP 2.03	Supply, place and compact 150mm of granular A	tonne	12,150		
B.03 SP 2.10	Supply, place and compact granular for shouldering	tonne	1,800		
B.04 SP 2.04	Supply, place and compact 75mm HL4	tonne	4,380		
B.05 SP 2.05	Driveway restoration - Asphalt	m2	150		
B.06 SP 2.06	Driveway restoration - Gravel	ea.	15		
B.07 SP 2.07	Driveway restoration - Interlock	m2	75		
B.08 SP 2.08	Driveway restoration - Concrete	m2	75		
B.09 SP 2.14	3 Cable Guiderail	m	402		
B.10 SP 2.11	Supply, Place and Compact Asphalt Gutter	m	1,000		
B.11 SP 2.12	Supply, Place and Compact Asphalt Spillway	ea.	10		
B.12 SP 2.17	Remove and Replace 1700mm culvert	ls	1		
B.13 SP 2.18	Supply and place Rip-Rap	m2	40		

PART F

Bass Lake Side Road - Line 13 to Line 14

Item	Description	Unit	Estimated Quantity	Unit Rate	Total
F.01 SP 2.01	Pulverize existing asphalt 150mm	m2	8,750		
F.02 SP 2.03	Supply, place and compact 150mm of granular A	tonne	4,250		
F.03 SP 2.10	Supply, place and compact granular for shouldering	tonne	675		
F.04 SP 2.04	Supply, place and compact 75mm HL4	tonne	1,640		
F.05 SP 2.05	Driveway restoration - Asphalt	m2	400		
F.06 SP 2.06	Driveway restoration - Gravel	ea.	4		
F.07 SP 2.09	Remove and replace culverts	ea.	1		
F.08 SP 2.15	Adjust Existing Mailbox	ea	4		
F.09 SP 2.16	Line Painting	lm.	1300		
F.10 SP 2.13	Material Transfer Vehicle	ls	1		
				TOTAL PART 'F'	